

Man Hour Summary - Item Totals

Project: MAIN_ST

ItemNumber	Description	# - Used	Takeoff Quantity	U/M	Man Hours
101	Box out excavation	1.00	3,126.75	CYS	280.00
201.01.1	8 in SDR 35 PVC 10 ft deep	1.00	500.00	LF	180.00
201.01.2	8 in SDR 35 PVC 15 ft deep	1.00	250.00		144.00
301.05.1	Rough grade	1.00	6,700.00	SY	120.00
301.05.2	Fine Grade	1.00	6,700.00	SY	160.00
401.01	Base Asphalt	1.00	1,000.00	TONS	128.00
501.01	Top Asphalt Course	1.00	410.00	TONS	264.00
INDIRECT	INDIRECT ITEM		1.00		
sawcut	Sawing pavt	1,000.00	1.00	lf	32.00
Total Man Hours					1,308.00